REQUEST FOR BIDS
Byrd Avenue Sewer Main Up-Grade

Proposals for upgrade of the sewer main for Byrd Avenue will be received by the Town of Berryville Business Office, located in the Berryville Clarke County Government Center, 101 Chalmers Court, Suite A, Berryville Virginia until 2:00 pm local time, Friday February 17th, 2012 at which time bids will be read opened and read aloud. The Town reserves the right to accept or reject any and all bids and to waive any irregularities therein.

Successful bidder will be required to furnish a Certificate of Insurance, Bid Bond for 5% of the total amount of the bid, Contractor's Performance Bond and Payment Bond, each in the amount of 100 percent of the contract price with a corporate surety approved by the owner within ten {10} days of Notice of Award.

This project will be done in accordance with an approved VDOT Land Use Permit, which the Town will acquire. ***All pipe installation and workmanship shall be in accordance with the Town of Berryville Construction Standards and Specifications, except where otherwise indicated with an asterisk (*), a current copy of these Standards can be obtained from the Town's Planning Department.*** All work on VDOT'S right of way shall be done in accordance to their current Standards and Specifications.

The asterisk (*) symbol represents material requested to be installed that is not listed in our current Standards & Specifications.

A Pre-Bid meeting will be held on site on Monday February 13th at 10:00 am. Attendance at this meeting is strongly recommended

Scope of Work

Excavate approximately {485 lf} of existing eight inch terracotta sewer main and replace with eight-inch * SDR 35 PVC. Stone bedding and backfill will be done per current Town Standards.

Excavate and replace three existing manholes. Approximately {9.6lf}

Excavate and replace up to eight {8} existing four inch short side laterals. Approximately {70 lf} and install a clean-out at the property line per Construction Standards Detail. * All cleanouts shall be backfilled with # 68 stone to within one foot of the finished grade.

Excavate and replace up to eight {8} existing four inch long side laterals. Approximately {215 lf} and install a clean-out at the property line per Construction Standards Detail. * All cleanouts shall be backfilled with # 68 stone to within one foot of finished grade.

All pipe footage and manhole depths as measured by the Town are approximate. It will be the bidder's responsibility to verify all pipe footage and manhole depths. This verification can occur following the pre-bid meeting.

All lateral road crossing's will be backfilled with 21B stone and compacted per VDOT'S specifications. All existing asphalt driveways will be asphalted to match existing thickness or 1.5 inches of SM2A whichever is greater. All lateral road crossings will have three inches of base asphalt installed. Once

all lateral road crossings are asphalted and approved by VDOT'S inspector, an overlay of 1.5 inches of SM2A asphalt will be applied. Footage of overlay approximately {500 lf long x 19 lf wide} footage will be identified prior to pre bid meeting.

Contractor shall locate existing water service lines and sanitary laterals ahead of construction so as not to interrupt service. Any service lines damaged as a result of construction shall be replaced by the contractor at no cost to the owner.

Contractor shall coordinate the work with the Town of Berryville Public Works Department. No work shall we be allowed on weekends or holidays. During construction it may be necessary to restrict excavation in the roadway for a short time period, this restriction if necessary will not exceed two {2} days. . A 48 hour notice will be given if this restriction is necessary.

No more than Three {3} payments maybe be requested. Payments shall be made on the basis of work actually performed such as pipe installation, manhole replacement, restoration of asphalt, and top-soil and seeding.

Ten {10%} of the contract price shall be retained by the owner until all installation meets the Towns Standards and passes all required testing as set forth in the Construction and Specification Manual. All VDOT permit requirements must meet their Standards and be approved and accepted before final payment is made.

All work must be completed within 90 days of notice of award.

Bid Form

*Eight inch * SDR 35*	*$_____*	*per lf*
Sanitary Manhole	*$_____*	*per lf*
*Four inch * SDR 35 lf*	*$_____*	*per lf*
*Eight x Four inch * SDR 35 Tee*	*$_____*	*per ea.*
Four inch 45 degree bend SDR 35*	*$ _____*	*per ea.*
*Four inch tee-wye * SDR 35*	*$_____*	*per ea.*
Four inch Brass clean out cap	*$_____*	*per ea.*
Lamp pole frame & cover	*$_____*	*per ea.*
Stone # 68	*$ _____*	*per ton*
Stone # 21B	*$_____*	*per ton*
Base asphalt	*$ _____*	*sq.yd.*
SM2A Asphalt	*$ _____*	*sq. yd.*
Top-soil and seed	*$_____*	*sq. yd.*

Total Bid *$ _____*